MYSORE PUBLIC WORKS DEPARTMENT.

(ELECTRICAL BRANCH.)

Bangalore Power and Lighting Scheme.

Dated 5th May 1904.

Notice is hereby given that sealed tenders will be received at the office of the Chief Electrical Engineer to the Government of Mysore, up to 31st May 1904, for constructing three buildings in connection with Bangalore Power and Lighting Scheme, in Bangalore.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1904.

2. The plans, detailed estimate, and conditions may be seen at the Chief Electrical Engineer's Office at Bangalore, between the hours of 2 and 4 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Chief Electrical Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for Buildings in connection with Bangalore, Power and Lighting," in default of which tenders will be rejected.

5. The first acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. Competitors, whether successful or not, will be notified of the acceptance or otherwise of their tenders in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Detailed abstract estimate of constructing Buildings for Bangalore, Power and Lighting Works.

Items of work.	*Per.*	*Quantity.*
No. 1 Station to be located near Fort, Bangalore City—		
1. Earthwork, excavating and filling in basement	C. yd.	176
2. Concrete foundation	C. ft.	530
3. Stone in mortar	„	10269
4. Slab stones, 6″ thick, roughly dressed	„	356
5. Brick archwork in cement	„	316
6. Stone ashlar work	„	189
7. Stone slabs, 6″ thick, neatly dressed and chamfered ...	„	100
8. Cement pointing	Sqr.	86·13
9. Cement plastering	„	5·42
10. Mangalore tile flooring under 6″ concrete	„	10·02
11. Mangalore tile roofing with ceiling tiles	„	19·68
12. Galvanized corrugated iron roofing	„	3·06
13. Teakwood work	„	218·00
14. Iron trusses 31 ft. clear span	Each	3
15. Carriage, hoisting and fixing charges for above ...	Lump sum.	
16. Iron trusses for lean-to roof	Each	3
17. Carriage, hoisting and fixing charges for above... ...	Lump sum.	
18. Teakwood doors	S.ft.	117
19. Teakwood windows	„	654
20. Circular ventilators	„	14
21. Ornamental finials	Each	2
22. Ornamental eave and barge boards 12″ × 1″	R.ft.	178
23. Cast iron columns about 9′ high	Each	5
24. Rolled iron beams including carriage	Cwt.	32·42
24*a*. Hoisting and fixing above	Lump sum.	
25. Cuddappah slab flooring 2″ thick	Sqr.	4·37
26. Ornamental hand railing 3′ high	R.ft.	60
27. Ornamental eave boards to gallery	„	65
28. Staircase 9′ high and 2½′ wide	Lump sum.	
29. Iron ladder about 10′ long	Do	
30. Painting	Sqr.	50·00

No. 2 and 3 Stations.—One on the maidan near Mayo Hall, the other on St. John's Hill—

(Approximate quantities for one building.)

Earthwork	C.yd.	86
Concrete foundation	C.ft.	359
Stone in mortar	„	6018
Stone slabs, 6″ thick, roughly dressed	S.ft.	202
Brick in cement archwork	C.ft.	279
Stone ashlar work	„	137
Stone slabs, 6″ thick, neatly dressed and chamfered	„	109
Cement pointing	Sqr.	56·80
Do plastering	„	4·80
Mangalore tile flooring over 6″ concrete	„	5·06
Do roofing with ceiling tiles, etc., complete	„	13·49
Teakwood work	C.ft.	150·43
Iron trusses 26′ clear span	No.	2
Carriage, hoisting and fixing charges of above	Lump sum.	
Doors, teakwood	S.ft.	89
Windows, teakwood	„	553
Circular ventilators	„	14
Ornamental finials	No.	2
Ornamental eave and barge boards 12″ × 1″	S.ft.	147
Cast iron columns about 9′ high	No.	4
Rolled iron beams including casting, etc.	Cwt.	29·22
Hoisting and fixing above	Lump sum.	
Cuddappah slabs, flooring (2″ thick)	Sqr.	3·52
Ornamental hand railing 3′ high	S. ft.	43
Ornamental eave board to gallery	„	43
Staircase 2½′ × 9′	Lump sum.	
Painting	Sqr.	30·00

H. P. GIBBS,
Chief Electrical Engineer to the Govt. of Mysore.

BANGALORE CITY MUNICIPALITY.

PROCEEDINGS OF AN ORDINARY MEETING OF THE MUNICIPAL COMMISSIONERS FOR THE CITY OF BANGALORE, HELD AT THEIR OFFICE PREMISES AT 8 A.M., ON THURSDAY THE 21ST APRIL 1904.

President—Absent, on other duty.
Vice-President—Present.

Ex-Officio Members.

Absent—The Sr. Surgeon and Sanitary Comr. with the Govt. of Mysore.
Do—The Executive Engr., Bangalore Dn.
Absent—The Principal, Central College.
Do—The Amildar, Bangalore Taluk.

Municipal Commissioners.

I—Palace Division.

Absent—I. Bronson, Esq.
Do—Aga Abdulla Saheb, Esq.

II—Bale Pete Division.

Absent—B. Gangiah, Esq.
Present—D. Venkataramaiya, Esq., B.A.

III—Munavarte Pete Division.

Absent—Veerabhadra Chetty, Esq.
Do—C. Krishna Murti, Esq.

IV—Ulsur Pete Division.

Absent—Boppannanavara Basanna, Esq.
Do—P. Narainsami Chetty, Esq.

V—Nagarth Pete Division.

Absent—B. V. Ramaswami Chetty, Esq. B.A.
Do—V. Chikkabasanna, Esq.

VI—Lal-Bagh Division.

Absent—J. Cameron, Esq., F.L.S.
Present—D. B. Ramachendra Mudaliar, Esq.

VII—Fort Division.

Present—B. Appajappa, Esq.
Absent—A. Somasundra Mudaliar, Esq.

VIII—Basavanagudi Division.

Present—M. K. Krishna Murti Rao, Esq.
Absent— Mahomed Ebrahim Saheb, Esq.

IX—Malleswaram Division.

Absent—S. Venkatarangiengar, Esq.
Present—P. R. Subramanaiya Sastri, Esq., B.A.

1. Read Cash Account Current, Demand, Collection and Balance Statements, Mortuary return, Progress report of works, Memo of visitors to the Srinivasa Mandiram Library, City Municipal English and Kanarese Schools returns, Langarkhana return, Statement of materials and Statement of rewards for the destruction of dogs, for March 1904.

Resolution.—Passed.